




Quality Engineer Services Since 1959
Consultants • Mechanical • Electrical • Civil

DAVID L. DAHL, P.E.
 MICHAEL J. MATHIAS, P.E.
 RICHARD A. BURCH, P.E.
 JOHN W. WETZEL, P.E.

SUSAN M. ARVIN, P.E.
 R. DERICK WIGGINS, P.E.
 BRIAN A. BULLOCK, P.E.
 NATHAN J. WALKER, P.L.S.
 R. AARON DERR, P.E.

EMERITUS
 ROBERT J. ELLIOTT, P.E.
 ARTHUR R. BOODY, P.E.
 JAMES E. BURCH, P.E.
 WM. DALE MEYER, P.E.

January 9, 2008

Loogootee Community School Corporation
 P.O. Box 282
 201 Brooks Avenue
 Loogootee, IN 47553

Attn: Larry Weitkamp, Supt.

RE: Storm Water Drainage Improvements
 City of Loogootee, Martin County, Indiana
 MEI Project No.: 200522

Dear Mr. Weitkamp,


At your request, and on behalf of the City of Loogootee, Midwestern has transmitted construction costs to extend the twin 48" diameter pipe 330' (648 L.F. total) across the school property. The extension of the underground pipe will allow for future extension of the parking area to the west of the Jr. High School. We have included a map for your use and review.

If the school were to proceed with this improvement, we request a payment in the amount of \$67,726.58 be sent to the City of Loogootee by February 1, 2008. If the extension is limited to 200 L.F. (388 L.F. total) the required deposit of funds is \$44,266.78. The City, in turn, will Change Order the project with the Contractor and proceed to construct this spring.

You should call me anytime, if you have any questions.

Sincerely,

MIDWESTERN ENGINEERS, INC.


 Michael J. Mathias, P.E.
 Senior Project Engineer

MJM/acw

Enclosures

cc: Mayor Don Bowling, w/attachments

U.S. 50 WEST • P.O. BOX 295 • LOOGOOTE, IN 47553-0295 • PHONE 812-295-2800 • FAX 812-295-2801
 E-MAIL meinc@midwesterneng.com • WEBSITE www.midwesterneng.com

CONSTRUCTION COSTS
FOR
TWIN 48" DIAMETER DRAINAGE PIPE EXTENSIONS
FOR
LOOGOOTEE COMMUNITY SCHOOL CORPORATION
CITY OF LOOGOOTEE, MARTIN COUNTY, INDIANA
JANUARY 9, 2008

(1) EXTEND PIPE 330' (660 TOTAL FEET)

ITEM NO.	DESCRIPTION	ESTIMATED QUANTITY	UNIT PRICE	TOTAL PRICE
1.	LINEAR DITCH GRADING	330 L.F.	\$8.30	(\$2,739.00)
2.	48" DIAMETER REINFORCED CLASS III CONCRETE PIPE	648 L.F.	\$94.38	\$61,158.24
18.	MANHOLE, TYPE K W/TYPE 7 CASTING	2 EA.	\$4,653.67	\$9,307.34
TOTAL CONSTRUCTION COST				\$67,726.58

(2) EXTEND PIPE 200 L.F. (400 TOTAL FEET)

1.	LINEAR DITCH GRADING	200 L.F.	\$8.30	(\$1,660.00)
2.	48" DIAMETER REINFORCED CLASS III CONCRETE PIPE	388 L.F.	\$94.38	\$36,619.44
18.	MANHOLE, TYPE K W/TYPE 7 CASTING	2 EA.	\$4,653.67	\$9,307.34
TOTAL CONSTRUCTION COST				\$44,266.78



106 S. Washington St.
P.O. Box 295
Dale, IN 47523

Proposal

Proposal Date: 1/9/2008

Proposal #: 4619

Project: HS Extension

Bill To:

City of Loogootee
High School Extension
Loogootee, IN 47553

Phone:	Fax:	E-mail
812 937-2722	812 937-2222	qualitycraft@psci.net

Description	Est. Hrs/...	U/M	Rate	Total
48" reinforced, class III concrete pipe	648	ft	94.38	61,158.24
Manhole, type "K" with type "7" casting	2	ea	4,653.67	9,307.34
Linear ditch grading and clearing	-330	ft	8.30	-2,739.00
Extend proposed twin 48" RCP an additional 330 LF at Loogootee High School. Relocate proposed endsection to the new location, terminating the additional storm sewer.				
			Total	\$67,726.58